



NOTE: THE PROPOSED BACK OF WALK WILL BE LOCATED 1.00' FROM THE EXISTING R/W LINE. CHANGES TO THIS LOCATION CAN BE DONE ONLY WITH PERMISSION OF THE VILLAGE ENGINEER.

ALL DISTURBED TURF ALONG THE NEW SIDEWALK WILL BE RESTORED WITH EITHER 4" OF NEW TOPSOIL AND SOD OR 4" OF NEW TOPSOIL AND HYDROSEED.

TYING NEW SIDEWALK TO EXISTING SIDEWALK WILL BE DONE BY INSTALLING 3-NO. 5 EPOXY COATED REBAR DRILLED IN TO THE EXISTING WALK PAVEMENT AT AN EQUAL SPACING AND A MINIMUM OF 4"

NOT TO SCALE



STANDARD DETAIL SIDEWALK DETAIL-CONCRETE

APPROVED 2/2006 REVISED 9/28/2018 RCB